

SCHEDULE OF REQUIREMENT

Name of work : Establishing KABADI COURT at Army Public School, K Kamaraj Road, Bangalore-42

Ser No	Description of work	Cost
1.	<u>Concrete Area</u> : 19x18Mtr = 342 Sq Mtr. Concrete should be 6 inch height (2" 40mm Aggregate and 4"20MM Aggregate)	
2.	<u>Mat Area</u> : 17 x 16 Mtr = 272 Sq Mtr. Mat should be 1 Mtr x Mtr interlocking and 30MM thickness. Density 100 Kgs/Cbm	
3.	<u>TEAM BENCH</u> :2 X Iron Bench 6 feet x 18 Inches Sitting Area, 6 Nos 18 gauge Squire Iron legs 304 Steel Plate for seating .	
4.	<u>SCORER's TABLE:</u> 1 X Iron Bench 4 feet x 18 Inches Sitting Area, 4 Nos 18 gauge Squire Iron legs 304 Steel Plate for Seating .	
5.	<u>SITTING BLOCK:</u> 2 X Iron Bench 6 feet x 18 inches Sitting Block, 6 Nos 18 gauge Squire Iron legs 304 Steel Plate for seating.	